

Sizewell C Notice to Mariners No 29 of 2026

Phase 2 of Marine Bulk Importing Facility (MBIF) Works

Mariners are advised that -

On or about the 2nd July 2026, phase 2 of the works to construct the Marine Bulk Import Facility (MBIF) are scheduled to commence within the Sizewell C Harbour and will continue for approximately 4 months.

This phase of the works will include the completion of construction of the MBIF jetty head and will be carried out from the self-propelled Jack-up Vessel **Wind** (pictured below).



At the same time the construction of the approach trestle connecting the jetty head and vessel berth with the terrestrial main build area and will begin from the main site to seaward utilising the Canti-travel process.

Both packages of works will be contained within SZC Marine Construction Zone as shown in the chartlet above.



J/U Wind

- Classification DNV GL – 1A1 self-elevating offshore support unit DYNPOS-AUT
- Dimensions L 55.1m, W 18.1m, Hull Depth 4m
- Accommodation for 28 persons
- Navigation and comms system
- Max Dead Weight 220t

The **Wind** may be serviced by the CTV Celtic Guardian (pictured)



Celtic Guardian

- 14m Cabin RIB
- Dimensions L 13.9m, W 4.3m, Draft 0.7m
- PAX 12 plus 2 crew
- Bow loading platform, Navigation and Comms system
- 9.5t fully loaded

Mariners are requested to exercise additional vigilance and maintain an effective lookout when transiting the harbour during this period of raised marine activity. All vessels engaged in this operation will abide by and display shapes and lights required by the COLREGS. Vessels will monitor VHF Channels 12 & 16.

Notices to Mariners in Force

2024: No15 of 2024, No19 of 2024. **2025:** No10 of 2025. **2026:** No6 of 2026, No7 of 2026, No11 of 2026, No12 of 2026, No14 of 2026, No26 of 2026.